

NOTICE

This scan only represents the application as filed. The information contained herein meets the requirements of K.A.R. 5-3-1 or K.A.R. 5-5-1, and has been found acceptable for filing in the office of the Chief Engineer. The application should not be considered to be a complete application as per K.A.R. 5-3-1b or K.A.R. 5-5-2a.

Submit To: CHIEF ENGINEER
Division of Water Resources
Kansas Department of Agriculture
1320 Research Park Drive
Manhattan, Kansas 66502
http://agriculture.ks.gov/dwr

**APPLICATION FOR APPROVAL TO
CHANGE THE PLACE OF USE, THE
POINT OF DIVERSION OR THE USE
MADE OF THE WATER UNDER AN
EXISTING WATER RIGHT**



State of Kansas

Filing Fee Must Accompany the Application
(Please refer to Fee Schedule on signature page of application form.)

Paragraph Nos. 1, 2, 3, 4 & 8 must be completed. Complete all other applicable portions. A topographic map or detailed plat showing the authorized and proposed points(s) of diversion and /or place of use must accompany this application.

1. Application is hereby made for approval of the Chief Engineer to change the

Place of Use

(Check one or more) Point of Diversion

Use Made of Water

WATER RESOURCES
RECEIVED
MAR 27 2023
1233
KS DEPT OF AGRICULTURE

File No. 519

2. Name of applicant: City of Garden City, Attention Water Department

Address: PO Box 998, 301 N 8th St

City, State and Zip: Garden City, KS 67846

Phone Number: (620)276-1291

E-mail address: fred.jones@gardencity.ks.us

What is your relationship to the water right; owner tenant agent other? If other, please explain. _____

Name of water use correspondent: SAME

Address: _____

City, State and Zip: _____

Phone Number: (____) _____

E-mail address: _____

3. The change(s) proposed herein are desired for the following reasons (please be specific): _____

Lose of production due to mechanical failure in current and need to relocate. Not adequate space on current property

The change(s) (was) (will be) completed by As soon as approved

(Date)

For Office Use Only:

F.O. 4 GMD 3 Meets K.A.R. 5-5-1 (YES/NO) Use MUN Source G/S County FL By ALB Date 3/28/23
Code CGT Fee \$ 200 TR # _____ Receipt Date 3/27/23 Check # 139398

3/29/2023
LMoody

4. The presently authorized place of use is:

Owner of Land — NAME: No Change

ADDRESS: _____

Sec.	Twp.	Range	NE¼				NW¼				SW¼				SE¼				TOTAL ACRES		
			NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼			

List any other water rights that cover this place of use. _____

Owner of Land — NAME: _____

ADDRESS: _____

Sec.	Twp.	Range	NE¼				NW¼				SW¼				SE¼				TOTAL ACRES			
			NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼				

List any other water rights that cover this place of use. _____

(If there are more than two landowners, attach additional sheets as necessary.)

5. It is proposed that the place of use be changed to:

Owner of Land — NAME: _____

ADDRESS: _____

Sec.	Twp.	Range	NE¼				NW¼				SW¼				SE¼				TOTAL ACRES				
			NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼					

List any other water rights that cover this place of use. _____

Owner of Land — NAME: _____

ADDRESS: _____

Sec.	Twp.	Range	NE¼				NW¼				SW¼				SE¼				TOTAL ACRES					
			NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼	NE¼	NW¼	SW¼	SE¼						

List any other water rights that cover this place of use. _____

6. The presently authorized point(s) of diversion (is) (are) 7 wells and discharge
(Provide description and number of points)

7. The proposed point(s) of diversion (is) (are) 7 wells and discharge
(Provide description and number of points)

List all presently authorized point(s) of diversion:

8. **Presently authorized point of diversion:**
 One in the _____ Quarter of the _____ Quarter of the SW Quarter
 of Section 17, Township 24 South, Range 32 W,
 in Finney County, Kansas, 2515 feet North 3330 feet West of Southeast corner of section.
 Authorized Rate 1736gpm Authorized Quantity 547.7mgv blanket authority
 (DWR use only: Computer ID No. 22 GPS _____ feet North _____ feet West)
 This point will not be changed This point will be changed as follows:
Proposed point of diversion: (Complete only if change is requested)
 One in the _____ Quarter of the _____ Quarter of the _____ Quarter
 of Section _____, Township _____ South, Range _____ (E/W),
 in _____ County, Kansas, _____ feet North _____ feet West of Southeast corner of section.
 Proposed Rate _____ Proposed Quantity _____
 This point is: Additional Well Geo Center List other water rights that will use this point _____

9. **Presently authorized point of diversion:**
 One in the _____ Quarter of the _____ Quarter of the SE Quarter
 of Section 17, Township 24 South, Range 32 W,
 in Finney County, Kansas, 1710 feet North 2175 feet West of Southeast corner of section.
 Authorized Rate 1736gpm Authorized Quantity 547.7mgv blanket authority
 (DWR use only: Computer ID No. 24 GPS _____ feet North _____ feet West)
 This point will not be changed This point will be changed as follows:
Proposed point of diversion: (Complete only if change is requested)
 One in the SE Quarter of the NW Quarter of the SE Quarter
 of Section 17, Township 24 South, Range 32 w,
 in Finney County, Kansas, 1734 feet North 1779 feet West of Southeast corner of section.
 Proposed Rate 1736gpm Proposed Quantity 547.7mgv blanket authority
 This point is: Additional Well Geo Center List other water rights that will use this point 519, 1230, 4665

10. **Presently authorized point of diversion:**
 One in the _____ Quarter of the _____ Quarter of the SE Quarter
 of Section 18, Township 24 South, Range 32 W,
 in Finney County, Kansas, 170 feet North 2035 feet West of Southeast corner of section.
 Authorized Rate 1736gpm Authorized Quantity 547.7mgv blanket authority
 (DWR use only: Computer ID No. 19 GPS _____ feet North _____ feet West)
 This point will not be changed This point will be changed as follows:
Proposed point of diversion: (Complete only if change is requested)
 One in the _____ Quarter of the _____ Quarter of the _____ Quarter
 of Section _____, Township _____ South, Range _____ W,
 in _____ County, Kansas, _____ feet North 2 feet West of Southeast corner of section.
 Proposed Rate _____ Proposed Quantity _____
 This point is: Additional Well Geo Center List other water rights that will use this point WATER RESOURCES

11. Describe the current condition of and future plans for any point(s) of diversion which will no longer be used. Proper plug once new well is completed

RECEIVED
MAR 27 2023

IF MORE SPACE IS NEEDED, ATTACH ADDITIONAL SHEETS AS NECESSARY

MAR 27 2023

APPLICATION FOR APPROVAL TO CHANGE
THE PLACE OF USE AND/OR POINT OF DIVERSION
SUPPLEMENTAL SHEET
FILE NO. 519

KS DEPT OF AGRICULTURE

Presently authorized point of diversion:

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section 18, Township 24 South, Range 20 W,
in Finney County, Kansas, 1950 feet North 1960 feet West of Southeast corner of section.

Authorized Rate 1040gpm Authorized Quantity 547.7mg blanket Depth of well _____ (feet)

(DWR use only: Computer ID No. 20 GPS _____ feet North _____ feet West)

This point will not be changed This point will be changed as follows: No change, point better described with GPS as follows:

Proposed point of diversion: (Complete only if change is requested or if existing point is better described by GPS)

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section _____, Township _____ South, Range _____ (E/W),
in _____ County, Kansas, _____ feet North _____ feet West of Southeast corner of section.

Proposed Rate _____ Proposed Quantity _____ Proposed well depth (feet) _____

This point is: Additional Well Geo Center List other water rights that will use this point _____

Presently authorized point of diversion:

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section 18, Township 24 South, Range 32 W,
in Finney County, Kansas, 2950 feet North 5000 feet West of Southeast corner of section.

Authorized Rate 1040gpm Authorized Quantity 547.7mg blanket Depth of well _____ (feet)

(DWR use only: Computer ID No. 22 GPS _____ feet North _____ feet West)

This point will not be changed This point will be changed as follows: No change, point better described with GPS as follows:

Proposed point of diversion: (Complete only if change is requested or if existing point is better described by GPS)

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section _____, Township _____ South, Range _____ (E/W),
in _____ County, Kansas, _____ feet North _____ feet West of Southeast corner of section.

Proposed Rate _____ Proposed Quantity _____ Proposed well depth (feet) _____

This point is: Additional Well Geo Center List other water rights that will use this point _____

Presently authorized point of diversion:

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section 13, Township 24 South, Range 32 W,
in Finney County, Kansas, 4980 feet North 1296 feet West of Southeast corner of section.

Authorized Rate 1040gpm Authorized Quantity 547.7mg blanket Depth of well _____ (feet)

(DWR use only: Computer ID No. 65 GPS _____ feet North _____ feet West)

This point will not be changed This point will be changed as follows: No change, point better described with GPS as follows:

Proposed point of diversion: (Complete only if change is requested or if existing point is better described by GPS)

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section _____, Township _____ South, Range _____ (E/W),
in _____ County, Kansas, _____ feet North _____ feet West of Southeast corner of section.

Proposed Rate _____ Proposed Quantity _____ Proposed well depth (feet) _____

This point is: Additional Well Geo Center List other water rights that will use this point _____

Presently authorized point of diversion:

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section 13, Township 24 South, Range 32 W,
in Finney County, Kansas, 2382 feet North 1047 feet West of Southeast corner of section.

Authorized Rate 1736gpm Authorized Quantity 480mg blanket Depth of well _____ (feet)

(DWR use only: Computer ID No. 67 GPS _____ feet North _____ feet West)

This point will not be changed This point will be changed as follows: No change, point better described with GPS as follows:

Proposed point of diversion: (Complete only if change is requested or if existing point is better described by GPS)

One in the _____ Quarter of the _____ Quarter of the _____ Quarter
of Section _____, Township _____ South, Range _____ (E/W),
in _____ County, Kansas, _____ feet North _____ feet West of Southeast corner of section.

Proposed Rate _____ Proposed Quantity _____ Proposed well depth (feet) _____

This point is: Additional Well Geo Center List other water rights that will use this point _____

IF MORE SPACE IS NEEDED, ATTACH ADDITIONAL SHEETS AS NECESSARY

12. The presently authorized use of water is for MUN purposes.
It is proposed that the use be changed to MUN purposes.
13. If changing the place of use and/or use made of water, describe how the consumptive use will not be increased.
No change needed for current consumptive use.
-
-
-

(Please show any calculations here.)

14. It is requested that the maximum annual quantity of water be reduced to _____ (acre-feet or million gallons).
15. It is requested that the maximum rate of diversion of water be reduced to _____ gallons per minute (____ c.f.s.).
16. The application must include either a topographic map or detailed plat. A U.S. Geological Survey Topographic Map, scale 1:24,000, is available through the Kansas Geological Survey, 1930 Constant Avenue, University of Kansas, Lawrence, Kansas 66047-3726 (www.usgs.gov). The map should show the location of the presently authorized point(s) of diversion. Distances North and West of the Southeast corner of the section must be shown. The presently authorized place of use should also be shown. Identify the center of the section, the section lines and the section corners and show the appropriate section, township, and range numbers on the map. In addition the following information must also be shown on the map.
- a. If a change in the location of the point(s) of diversion is proposed, show:
- 1) The location of the proposed point(s) of diversion. Distances North and West of the Southeast corner of the section must be shown. Please be certain that the information shown on the map agrees with the information shown in Paragraph Nos. 9, 10 and 11 of the application.
 - 2) If the source of supply is groundwater, please show the location of existing water wells of any kind, including domestic wells, within 1/2 mile of the proposed well or wells. Identify each well as to its use and furnish name and mailing address of the property owner or owners. If there are no wells within 1/2 mile, please indicate so on the map.
 - 3) If the source of supply is surface water, the names and mailing addresses of all landowner(s) 1/2 mile downstream and 1/2 mile upstream from your property lines must be shown.
- b. If a change in the place of use is desired, show the proposed place of use by crosshatching on the map. Please be certain that the information shown on the map agrees with the information shown in Paragraph No. 5 of the application.
17. Attach documentation to show the change(s) proposed herein will not impair existing water rights and relates to the same local source of supply as to which the water right relates. This information may include statements, plats, geology reports, well logs, test hole logs, and other information as necessary information to show the above. Additional comments may be made below.

See attached plat and supporting documentation

18. If the proposed change(s) does not meet all applicable rules and regulations of the Kansas Water Appropriation Act, please identify the rules and regulations for which you request a waiver. State the reason why a waiver is needed and why the request should be granted. Attach documentation showing that granting the request will not impair existing water rights and will not prejudicially and unreasonably affect the public interest.

Waiver needed for minimum spacing, KAR 5-23-3, not met at proposed location.

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE

IF MORE SPACE IS NEEDED, ATTACH ADDITIONAL SHEETS AS NECESSARY

Any use of water that is not as authorized by the water right or permit to authorize water **before** the chief engineer approves this application is a violation of the Kansas Water Appropriation Act for which criminal or civil penalties may be assessed. Such violation is a class C misdemeanor, punishable by a fine not to exceed \$500 and/or a term of confinement not to exceed one month in the county jail. K.S.A. 82a-728(b). Civil penalties shall be not less than \$100 nor more than \$1,000 per violation. In the case of a continuing violation, each day such violation continues may be deemed a separate violation. In addition to these penalties the water right may be modified or suspended. K.S.A. 82a-737, as amended.

The application must be signed by all owners of the place of use authorized under the water right and his or her spouse, if married. Please indicate if there is no spouse. If land is being purchased under contract, the seller must sign as landowner until such time as the contract is completed.

In the event that all applicants cannot appear before one notary public, they may as necessary sign separate copies of the application before any notary public conveniently available to them. All copies signed in this manner shall be considered to be valid parts of the application.

If the request is signed on behalf of any Owner by someone with legal authority to do so (for example, an agent, one who has power of attorney, or an executor, executrix, conservator), it will be necessary to attach proper documents showing such authority.

I declare that I am an owner of the currently authorized place of use as identified herein, or that I represent all such owners and am authorized to make this application on their behalf, and declare further that the statements contained herein are true, correct, and complete. By filing this application I authorize the chief engineer to permanently reduce the quantity of water and/or rate of diversion as specified in sections 14 and 15 of this application.

Dated at Garden City, Kansas, this 20th day of March, 2023.

City of Garden City, Kansas By: Fred Jones
(Owner)

(Spouse)

Fred Jones, Water Resource Mgr
(Please Print)

(Please Print)

(Owner)

(Spouse)

(Please Print)

(Please Print)

(Owner)

(Spouse)

(Please Print)

(Please Print)



Notary Public
State of Kansas
Kacy Quintana
My Commission Expires 10-29-24

State of Kansas)
County of Finney) SS

I hereby certify that the foregoing application was signed in my presence and sworn to before me this 20th day of March, 2023.

Kacy Quintana
Notary Public

My Commission Expires 10-29-24

FEE SCHEDULE

Each application to change the place of use, the point of diversion or the use made of the water under this section shall be accompanied by the application fee set forth in the schedule below:


- (1) Application to change a point of diversion 300 feet or less \$100
- (2) Application to change a point of diversion more than 300 feet \$200
- (3) Application to change the place of use \$200
- (4) Application to change the use made of the water \$300

Make check payable to **Kansas Department of Agriculture.**

WATER RESOURCES
RECEIVED

MAR 27 2023

Change App. PD, File No. 519



Scale: 1" = 2000'

Neighboring wells within half mile of City of Garden City proposed change to FI 01, 519, 1230 & 4665. All under ID 24. Proposed location is located 1734'N 1779'W in 17-24-32, Finney County.

FI 67 & 18608 D1: Robin L & Debra A Huber, PO Box 1359, Garden City, KS 67846

18608 D2: Deverne R Cartmill ET AL, 1112 Kingsury, Garden City, KS 67846

FI 218: Ehresman Packing Co, 912 E Fulton St, Garden City, KS 67846


Some of the wells, such as FI 52 are listed as "Verified Report DWR" and I am not certain how they handle those.

Some might have some old domestic wells in the area, but that is very hard to determine. With this being a City project, a notice in the paper could also serve as notice.

WATER RESOURCES
RECEIVED

MAR 27 2023

KC 211 - 01 - 01 - 01 - 01



Job Name Chestnut Deep
Location Garden City, KS
Driller Downey Drilling

Sample ID 010923-4
Analyzed by: Duvall, Steven
Date: 1/10/2023

Casing ϕ 16 in
Screen ϕ 16 in

Desired Yield 600 - 800 GPM
SWL (ft) 190

Recommended Slot Size: 60 slot (0.060") screen from 194'-207' & 229'-260' bgs.
Recommended Gravel Pack: P.W. Gillibrand 8 x 16 Rescreen

Based exclusively on the samples provided by the contractor, a sieve analysis graph and suggested screen slot size is provided as requested. Since numerous construction considerations and site circumstances influence successful well completion, Johnson Screens assumes no responsibility for final well performance nor awareness of local regulations pertaining to well installations.

C10923-4

SIEVE ANALYSIS INFORMATION

PLEASE FILL OUT THE FOLLOWING INFORMATION AND MAIL ALONG WITH YOUR SAMPLES TO:

Bilfinger Water Technologies / Johnson Screens
1950 Old Highway 8 NW
New Brighton, MN 55112
Phone - 651-638-3160

DRILLER: DOWNEY DRILLING, INC

ENGINEER: Carl Nazman (Geologist)

JOB NAME: Garden City Shrestant Deep

LOCATION: NWSE 17-24S-32W

TEST HOLES, DIAMETER: 6 1/4

TEST HOLES, DEPTH: 295

DRILLING METHOD: Mud Rotary

DRILLING FLUID: Quik Gel

DESIRED YIELD: 600 to 800

STATIC WATER LEVEL: 93'

WELL CASING DIAMETER: 16"

WELL SCREEN DIAMETER: 16"

WELL SCREEN LENGTH: 194-207 229-260

WELL APPLICATION: Municipal

DESIGN TYPE: Naturally Developed or Gravel Pack

SAMPLES SENT BY: DOWNEY DRILLING, INC

PURCHASE ORDER NO: 22-1437

COPIES TO BE SENT TO: DOWNEY DRILLING, INC
PO BOX 278
LEXINGTON, NE 68850

PHONE: 308-324-2303

FAX: 308-324-4825

EMAIL ADDRESS: T.DOWNEY@DOWNEYDRILLING.COM, B.DOWNEY@DOWNEYDRILLING.COM

COMMENTS: amessenger@downeydrilling.com

WATER RESOURCES
RECEIVED

MAR 27 2023

SIEVE ANALYSIS FORM 12/30/2022

KS DEPT OF AGRICULTURE



CUSTOMER NAME: CITY OF GARDEN CITY KS

LEGAL: NWSE 17-24S-32W

COUNTY: FINNEY

GPS: 37.57'55"N

100.51'12"W

FINNEY ST. SITE / CHESTNUT

DRILLER: RYAN

WO: 22-1437

V	FROM	TO	TYPE	HARDNESS	COLOR	SPEED	PULL DOWN	OTHER / DRILLING ACTION
	0	5	TOP SOIL	SOFT	DARK	FAST	NO	SMOOTH
	5	11	SANDY CLAY	SOFT	LI BR	FAST	NO	SMOOTH
	11	46	FINE-MED-COARSE GRAVEL	SOFT	RED/BR	FAST	NO	CHATTER
	46	73	SANDY CLAY	SOFT	LT BR	SLOW	NO	SMOOTH
	73	108	FINE-MED GRAVEL / THIN SANDY CLAY LAYERS	SOFT	RED/BR	FAST	NO	CHATTER
	108	136	SANDY CLAY / FINE-MED SAND	FIRM	LT BR	SLOW	NO	SMOOTH
	136	148	FINE-MED GRAVEL / THIN CLAY STRIPS	SOFT	RED/BR	FAST	NO	CHATTER
	148	190	FINE-MED GRAVEL	SOFT	RED/BR	FAST	NO	CHATTER
	190	194	SANDY CLAY	SOFT	LI BR	FAST	NO	SMOOTH
	194	207	MED-COARSE SAND / T FINE-GRAVEL / THIN CLAY LAYERS	SOFT	BR/RED	FAST	NO	CHATTER
	207	229	SANDY CLAY	SOFT	LT BR	FAST	NO	SMOOTH
	229	250	COARSE SAND / FINE GRAVEL	SOFT	BR/RED	FAST	NO	CHATTER
	250	254	SANDY CLAY	SOFT	LT BR	FAST	NO	SMOOTH
	254	260	COARSE SAND	SOFT	RED/BR	FAST	NO	CHATTER
	260	270	FINE-MED-COARSE SAND	SOFT	BR	FAST	NO	SLIGHT CHATTER
	270	276	SANDY CLAY	SOFT	LT BR	SLOW	NO	SMOOTH
	276	282	LIMESTONE / CLAY	HARD	WHITE	SLOW	YES	CHOPPY
	282	295	SHALE	HARD	BLACK		YES	SMOOTH
			3 CUPS SODA ASH					
			10 BAGS QUIK GEL					
			1 GALLON EZ MUD					
			#6 QUIK TROL LV					
			3000 GAL WATER					



Century GEOPHYSICAL CORP.

GARDEN CITY CHESTNUT SITE

COMPANY : DOWNEY DRILLING INC
 WELL : GARDEN CITY CHESTNUT SIT
 LOCATION/FIELD : TH #1 DEE
 COUNTY : FINNEY
 LOCATION : NWSE
 SECTION : 17

OTHER SERVICES:

TOWNSHIP : 24S RANGE : 32W

DATE : 12/02/22
 DEPTH DRILLER : 295
 LOG BOTTOM : 293.10
 LOG TOP : 0.30

PERMANENT DATUM : GL
 LOG MEASURED FROM: GL
 DRL MEASURED FROM: GL

KB :
 DF :
 GL :

CASING DIAMETER : 10.
 CASING TYPE :
 CASING THICKNESS:

LOGGING UNIT : 1903
 FIELD OFFICE : DDI
 RECORDED BY : BRENT

BIT SIZE : 6.25
 MAGNETIC DECL. : 0
 MATRIX DENSITY : 2.71
 NEUTRON MATRIX : LIMESTON

BOREHOLE FLUID : MUD
 RM :
 RM TEMPERATURE :
 MATRIX DELTA T : 49

FILE : ORIGINAL
 TYPE : 8144A
 LGDATE: 12/02/22
 LGTIME : 10:39:
 THRESH: 99999



N 37.57'55"
 W -100 51'12"


ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS

WATER RESOURCES
 RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE







WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE



0	API-GR	200
	GAMMA	
-700	MV	-500
	SP	



0	OHM-M	500	OHM	50
	RES(16N)		RES	
0	OHM-M	5055	DEG_F	65
	RES(64N)		TEMP	

0	OHM-M	10		0	OHM-M	50
	RES(FL)		FEET		LATERAL	

WATER RESOURCES
RECEIVED


MAR 27 2023

KS DEPT OF AGRICULTURE

TOQL CALIBRATION GARDEN CITY CHESTNUT SITE 12/02/22 10:39
TOOL 8144A TM VERSION 1
SERIAL NUMBER 365

	DATE	TIME	SENSOR	STANDARD	RESPONSE
1	Feb08,18	07:51:35	GAMMA	1.000 [API-GR]	4.000 [CPS]
	Feb08,18	07:51:35	GAMMA	340.000 [API-GR]	290.000 [CPS]
2	Jul12,17	13:24:17	RES(FL)	1.330 [OHM-M]	7595.000 [CPS]
	Jul12,17	13:24:17	RES(FL)	42.700 [OHM-M]	64820.000 [CPS]
3	Jan14,22	08:32:51	SP	0.000 [MV]	327768.000 [CPS]
	Jan14,22	08:32:51	SP	381.500 [MV]	164650.000 [CPS]
4	Jan14,22	08:33:01	RES(16N)	0.000 [OHM-M]	3453.000 [CPS]
	Jan14,22	08:33:01	RES(16N)	1951.500 [OHM-M]	448089.000 [CPS]
5	Jan14,22	08:33:10	RES(64N)	0.000 [OHM-M]	3163.000 [CPS]
	Jan14,22	08:33:10	RES(64N)	1994.000 [OHM-M]	449170.000 [CPS]
6	Jul12,17	13:17:49	TEMP	33.400 [DEG_F]	66910.000 [CPS]
	Jul12,17	13:17:49	TEMP	102.200 [DEG_F]	270930.000 [CPS]
7	Jan14,22	08:33:36	RES	0.000 [OHM]	21285.000 [CPS]
	Jan14,22	08:33:36	RES	944.000 [OHM]	190148.000 [CPS]

CORPORATE
75471 ROAD 435
LEXINGTON, NE 68850
308-324-2303



3210 ANTELOPE AVE. STE D
KEARNEY, NE 68847
308-237-9283

525 INDUSTRIAL DR
GARDEN CITY, KS 67846
620-277-7971

CITY OF GARDEN CITY
NWSE 17-24S-32W
FINNEY CO
CHESTNUT SITE
DEEP MONITORING WELL

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1678972 WELL ID _____

Original Record Correction Change in Well Use

LOCATION OF WATER WELL

Latitude	37.965278	Longitude	-100.853333	Section	17	Township	24	Range	32	<input type="checkbox"/> E <input checked="" type="checkbox"/> W	Fraction	SE ¼ NW ¼ SE ¼
Datum	NAD83	Elevation	2831	County	Finney							

WATER WELL OWNER

Name	
Business	CITY OF GARDEN CITY
Address	PO BOX 998 GARDEN CT KS 67846
Well location	238 FT SOUTH FROM E LAUREL ST, 300 FT EAST
<input type="checkbox"/> at owner's address	

WELL WATER USE

Other **PIEZOMETER**

COMPLETION

Depth of completed well: 250 ft.
 Depth(s) groundwater encountered:
 (1) _____ ft.; (2) _____ ft.;
 (3) _____ ft.; (4) dry well

Static water level in well: 93 ft.
 measured below land surface on (mm/dd/yy): 12/02/2022
 measured above land surface on (mm/dd/yy): _____

Estimated yield: _____ gpm
 Water level was: _____ ft. after _____ hours pumping _____ gpm
 Pump installed? Yes No

Water well disinfected? Yes No
 Date disinfected (mm/dd/yy): _____

Aquifer, if known: _____

NEAREST SOURCE OF POTENTIAL CONTAMINATION

Source: _____
 Distance from well: _____ Direction from well: _____
 Source description: _____
 Source: _____
 Distance from well: _____ Direction from well: _____
 Source description: _____
 No potential source of contamination within 100 feet.

CONSTRUCTION

Borehole interval: from 0 to 250 ft. Borehole diameter: 6.25 in.
 from _____ to _____ ft. _____ in.

Casing height above land surface: 31 in.
 If casing height is less than 12 in. has a variance been approved?* Yes No
 *variance not required for monitoring or environmental remediation wells

Casing type: ThermalPlastic

Blank casing interval: 0 ft. to 240 ft.
 Blank casing diameter: 2.38 in.
 Casing joints: Threaded
 Weight: .72 lbs/ft.
 Wall thickness or gauge no.: SCH 40

Blank casing interval: _____ ft. to _____ ft.
 Blank casing diameter: _____ in.
 Casing joints: _____
 Weight: _____ lbs/ft.
 Wall thickness or gauge no.: _____

Grout interval: 0 ft. to 230 ft.
 Grout material: Bentonite

Grout interval: _____ ft. to _____ ft.
 Grout material: _____

Screen / perforation material: PVC
 Screen / perforation openings: Continuous slot
 Screen / perforation intervals:
 From 240 ft. to 250 ft.
 Slot size .01 unit inches
 From _____ ft. to _____ ft.
 Slot size _____ unit _____

Gravel pack intervals:
 Gravel pack not used: Gravel size #40 in
 From 230 ft. to 250 ft.
 Gravel pack not used: Gravel size _____ in
 From _____ ft. to _____ ft.

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____
 KDHE / EPA Project Code: _____
 Site Name: CHESTNUT DEEP
 KDHE UIC Class V Form Completed: Yes No
 County Permit: Yes No Permit ID: _____
 Lease Name & Well #: _____
 # of boreholes: _____ # of dewatering wells: _____

LITHOLOGIC LOG


FROM	TO	LITHOLOGY INTERVALS
Attach	Attach	Attached

COMMENTS

CONTRACTOR'S OR LANDOWNERS CERTIFICATION

This water well was constructed reconstructed pursuant to the stated water well contractor's license and was completed on 12/02/2022. I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 01/09/2023 under the business name of Downey Drilling, Inc. #748, Kansas Water Well Contractor's License No. 748 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Thomas Downey.

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.



PROJECT
CITY OF GARDEN CITY, KS
COUNTY
FINNEY
LOGGED BY
ADAM

WELL NUMBER
DEEP - CHESTNUT
LAND LEGAL
NWSE 17-24S-32W
BOREHOLE DIA.
6.5"

DATE CONSTRUCTED
12/2/2022
TOTAL DEPTH
250'
GPS LOCATION
37.965278
100.853333

DRILLER
BRENT
METHOD
STR MUD ROTARY

<u>CASING</u>	
TYPE:	FLUSH JOINT PVC
DIAMETER:	2"
LENGTH:	243'

<u>SCREEN</u>	
TYPE:	FLUSH JOINT PVC
DIAMETER:	2"
LENGTH:	10'
SLOT SIZE	0.01

<u>FILTER PACK</u>	
TYPE:	#40 RED FLINT
AMOUNT:	1000#

<u>GROUT</u>	
TYPE:	NA
AMOUNT:	NA


<u>SEALS: AMT & TYPE:</u>	
BOT:	
MID:	0-230'
TOP:	
TYPE:	3500# HOLE PLUG

SITE#:	CHESTNUT
---------------	----------

TH#:	DEEP WELL
-------------	-----------

<u>WELL DEVELOPMENT</u>	
METHOD:	AIR LIFT
DURATION:	1 HOUR

<u>COMMENTS:</u>	
2X2 CONCRETE PAD	





Century GEOPHYSICAL CORP.

GARDEN CITY CHESTNUT SITE

COMPANY : DOWNEY DRILLING INC
 WELL : GARDEN CITY CHESTNUT SIT
 LOCATION/FIELD : TH #1 DEE
 COUNTY : FINNEY
 LOCATION : NWSE
 SECTION : 17

OTHER SERVICES:

TOWNSHIP : 24S RANGE : 32W

DATE : 12/02/22
 DEPTH DRILLER : 295
 LOG BOTTOM : 293.10
 LOG TOP : 0.30

PERMANENT DATUM : GL

KB :
 DF :
 GL :

LOG MEASURED FROM: GL
 DRL MEASURED FROM: GL

CASING DIAMETER : 10.
 CASING TYPE :
 CASING THICKNESS:

LOGGING UNIT : 1903
 FIELD OFFICE : DDI
 RECORDED BY : BRENT

BIT SIZE : 6.25
 MAGNETIC DECL. : 0
 MATRIX DENSITY : 2.71
 NEUTRON MATRIX : LIMESTON

BOREHOLE FLUID : MUD
 RM :
 RM TEMPERATURE :
 MATRIX DELTA T : 49

FILE : ORIGINAL
 TYPE : 8144A
 LGDATE: 12/02/22
 LGTIME : 10:39:
 THRESH: 99999

N 37.57'55"
 W -100 51'12"

ALL SERVICES PROVIDED SUBJECT TO STANDARD TERMS AND CONDITIONS

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE

Account No. : 41160

Water Analysis Report

DOWNEY DRILLING
PO BOX 278
LEXINGTON NE 68850-0278

Invoice No. : 1392001
Date Received : 12/19/2022
Date Reported : 12/20/2022

Lab Number : 30521

Results For : 22-1432

Location :

Sample ID : CN DEEP

pH	8.0
Total Dissolved Solids (TDS) Est, ppm	411
Electrical Conductivity, mmho/cm	0.69
Cations / Anions, me/L	8.1 / 7.5

	<u>ppm</u>
Sodium, Na	49
Potassium, K	4
Calcium, Ca	76.7
Magnesium, Mg	25
Total Hardness, CaCO ₃	297
Nitrate, NO ₃ -N	1.5 (SAFE)
Sulfate, SO ₄ -S	66
Chloride, Cl	24
Carbonate, CO ₃	< 1.0
Bicarbonate, HCO ₃	159
Total Alkalinity, CaCO ₃	131
Fluoride, F	0.64
Total Iron, Fe	< 0.01
Manganese, Mn	< 0.01

"<" - Not Detected / Below Detection Limit

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE


Reviewed By : Raymond Ward

12/23/2022

Copy : 1

Page 3 of 8

CORPORATE
75471 ROAD 435
LEXINGTON, NE 68850
308-324-2303



3210 ANTELOPE AVE. STE D
KEARNEY, NE 68847
308-237-9283

525 INDUSTRIAL DR
GARDEN CITY, KS 67846
620-277-7971

CITY OF GARDEN CITY
NWSE 17-24S-32W
FINNEY CO
CHESTNUT SITE
SHALLOW MONITORING WELL

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1678995 WELL ID _____

Original Record Correction Change in Well Use

LOCATION OF WATER WELL

Latitude	37.965272	Longitude	-100.853436	Section	17	Township	24	Range	32	<input checked="" type="checkbox"/> E <input checked="" type="checkbox"/> W	Fraction	SE ¼ NW ¼ SE ¼
Datum	NAD83	Elevation	2831	County	Finney							

WATER WELL OWNER

Name	
Business	CITY OF GARDEN CITY
Address	PO BOX 998 GARDEN CI KS 67846
Well location	238 FT SOUTH FROM E LAUREL ST, 280 FT EAST
<input type="checkbox"/> at owner's address	

WELL WATER USE

Other PIEZOMETER

COMPLETION

Depth of completed well: 155 ft.
 Depth(s) groundwater encountered:
 (1) _____ ft.; (2) _____ ft.;
 (3) _____ ft.; (4) dry well

Static water level in well: 87 ft.
 measured below land surface on (mm/dd/yy): 12/06/2022
 measured above land surface on (mm/dd/yy): _____

Estimated yield: _____ gpm
 Water level was: _____ ft. after _____ hours pumping _____ gpm
 Pump installed? Yes No

Water well disinfected? Yes No
 Date disinfected (mm/dd/yy): _____

Aquifer, if known: _____

NEAREST SOURCE OF POTENTIAL CONTAMINATION

Source: _____
 Distance from well: _____ Direction from well: _____
 Source description: _____

Source: _____
 Distance from well: _____ Direction from well: _____
 Source description: _____

No potential source of contamination within 100 feet.

CONSTRUCTION

Borehole interval: from 0 to 155 ft. Borehole diameter: 6.25 in.
 from _____ to _____ ft. _____ in.

Casing height above land surface: 32 in.
 If casing height is less than 12 in. has a variance been approved? Yes No
 *variance not required for monitoring or environmental remediation wells
 Casing type: ThermalPlastic

Blank casing interval: 0 ft. to 145 ft.
 Blank casing diameter: 2.38 in.
 Casing joints: Threaded
 Weight: .72 lbs/ft.
 Wall thickness or gauge no.: SCH 40

Blank casing interval: _____ ft. to _____ ft.
 Blank casing diameter: _____ in.
 Casing joints: _____
 Weight: _____ lbs/ft.
 Wall thickness or gauge no.: _____

Grout interval: 0 ft. to 140 ft.
 Grout material: Bentonite

Grout interval: _____ ft. to _____ ft.
 Grout material: _____

Screen / perforation material: PVC
 Screen / perforation openings: Continuous slot
 Screen / perforation intervals:
 From 145 ft. to 155 ft.
 Slot size .01 unit inches
 From _____ ft. to _____ ft.
 Slot size _____ unit _____

Gravel pack intervals:
 Gravel pack not used: Gravel size #40 in
 From 140 ft. to 155 ft.
 Gravel pack not used: Gravel size _____ in
 From _____ ft. to _____ ft.

LITHOLOGIC LOG

FROM	TO	LITHOLOGY INTERVALS
Attach	Attach	Attached

COMMENTS

CONTRACTOR'S OR LANDOWNERS CERTIFICATION

This water well was constructed reconstructed pursuant to the stated water well contractor's license and was completed on 12/06/2022. I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 01/09/2023 under the business name of Downey Drilling, Inc. #748, Kansas Water Well Contractor's License No. 748 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Thomas Downey.

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

Form	WWC5.2 - Water Well Record
Doc ID	1678995
Well Owner	CITY OF GARDEN CITY
Contractor	Downey Drilling, Inc. #748

Lithology

From	To	Lithology Intervals
0	5	topsoil,tan,soft
5	10	clay,red,soft
10	45	sand & gravel,fine to medium,red,soft
45	75	clay,fine to medium,sandy,tan,soft
75	110	sand & gravel,fine to coarse,red,soft
110	140	clay,fine to medium,sandy,tan,soft
140	146	sand & gravel,fine to coarse,red,soft
146	148	clay,tan,soft
148	155	sand & gravel,fine to medium,red,soft

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE



PROJECT
CITY OF GARDEN CITY
COUNTY
FINNEY
LOGGED BY
ADAM

WELL NUMBER
SHALLOW / CHESTNUT
LAND LEGAL
NWSE 17-24S-32W
BOREHOLE DIA.
6.25"

DATE CONSTRUCTED
12/6/2022
TOTAL DEPTH
155'
GPS LOCATION
37.965272
100.853436

DRILLER
RYAN
METHOD
STRAIGHT MUD

CASING
TYPE: FLUSH JOINT PVC
DIAMETER: 2"
LENGTH: 145' + 32"

SCREEN
TYPE: FLUSH JOINT PVC
DIAMETER: 2"
LENGTH: 10'
SLOT SIZE 0.01

FILTER PACK
TYPE: #40 RED FLINT
AMOUNT: 1200 LBS

GROUT
TYPE:
AMOUNT:

SEALS: AMT & TYPE:
BOT:
MID: 0-140'
TOP:
TYPE: 3/4" HOLE PLUG


SITE#: CHESTNUT

TH#: SHALLOW

WELL DEVELOPMENT
METHOD: AIR LIFT
DURATION: 1 HOUR

COMMENTS:

2X2 CONCRETE PUD
1 WELL PROTECTOR



WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE

Account No. : 41160

Water Analysis Report

DOWNEY DRILLING
PO BOX 278
LEXINGTON NE 68850-0278

Invoice No. : 1392001
Date Received : 12/19/2022
Date Reported : 12/20/2022

Lab Number : 30520

Results For : 22-1432

Location :

Sample ID : CN SHALLOW

pH	7.6
Total Dissolved Solids (TDS) Est, ppm	1632
Electrical Conductivity, mmho/cm	2.72
Cations / Anions, me/L	35.6 / 35.7

	<u>ppm</u>
Sodium, Na	352
Potassium, K	9
Calcium, Ca	291.5
Magnesium, Mg	66
Total Hardness, CaCO ₃	1005
Nitrate, NO ₃ -N	6.3 (SAFE)
Sulfate, SO ₄ -S	443
Chloride, Cl	107
Carbonate, CO ₃	< 1.0
Bicarbonate, HCO ₃	271
Total Alkalinity, CaCO ₃	223
Fluoride, F	0.14
Total Iron, Fe	< 0.01
Manganese, Mn	< 0.01

"<" - Not Detected / Below Detection Limit


Reviewed By : Raymond Ward

12/23/2022

Copy : 1

Page 2 of 8

CORPORATE
75471 ROAD 435
LEXINGTON, NE 68850
308-324-2303



3210 ANTELOPE AVE. STE D
KEARNEY, NE 68847
308-237-9283

525 INDUSTRIAL DR
GARDEN CITY, KS 67846
620-277-7971

CITY OF GARDEN CITY
NWSE 17-24S-32W
FINNEY CO
CHESTNUT SITE
MIDDLE MONITORING WELL

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1678985 WELL ID

Original Record Correction Change in Well Use

LOCATION OF WATER WELL

Table with columns: Latitude, Longitude, Section, Township, Range, Fraction, Datum, Elevation, County. Values include 37.96528, -100.853391, 17, 24, 32, SE 1/4 NW 1/4 SE 1/4, NAD83, 2832, Finney.

WATER WELL OWNER

Name: CITY OF GARDEN CITY
Business: CITY OF GARDEN CITY
Address: PO BOX 998, GARDEN CT KS 67846
Well location: 238 FT SOUTH FROM E LAUREL ST, 280 FT EAST

WELL WATER USE

Other PIEZOMETER

COMPLETION

Depth of completed well: 200 ft.
Depth(s) groundwater encountered: (1) ft.; (2) ft.; (3) ft.; (4) dry well
Static water level in well: 87.9 ft.
measured below land surface on (mm/dd/yy): 12/05/2022
measured above land surface on (mm/dd/yy):
Estimated yield: gpm
Water level was: ft. after hours pumping gpm
Pump installed? Yes No
Water well disinfected? Yes No
Date disinfected (mm/dd/yy):
Aquifer, if known:

NEAREST SOURCE OF POTENTIAL CONTAMINATION

Source:
Distance from well: Direction from well:
Source description:
Source:
Distance from well: Direction from well:
Source description:
No potential source of contamination within 100 feet.

CONSTRUCTION

Borehole interval: from 0 to 200 ft. Borehole diameter: 6.25 in.
Casing height above land surface: 32 in.
Casing type: ThermalPlastic
Blank casing interval: 0 ft. to 190 ft.
Blank casing diameter: 2.38 in.
Casing joints: Threaded
Weight: .72 lbs/ft.
Wall thickness or gauge no.: SCH 40
Grout interval: 0 ft. to 185 ft.
Grout material: Bentonite
Screen / perforation material: PVC
Screen / perforation openings: Continuous slot
Screen / perforation intervals: From 190 ft. to 200 ft.
Slot size .01 unit inches
Gravel pack intervals: Gravel pack not used: Gravel size #40 in
From 185 ft. to 200 ft.

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.:
KDHE / EPA Project Code:
Site Name: CHESTNUT MIDDLE
KDHE UIC Class V Form Completed: Yes No
County Permit: Yes No Permit ID:
Lease Name & Well #:
of boreholes: # of dewatering wells:

LITHOLOGIC LOG

Table with columns: FROM, TO, LITHOLOGY INTERVALS. Row 1: Attached, Attached, Attached.

COMMENTS

Empty box for comments.

CONTRACTOR'S OR LANDOWNERS CERTIFICATION

This water well was constructed reconstructed pursuant to the stated water well contractor's license and was completed on 12/05/2022. I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 01/09/2023 under the business name of Downey Drilling, Inc. #748, Kansas Water Well Contractor's License No. 748 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Thomas Downey.

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

Form	WWC5.2 - Water Well Record
Doc ID	1678985
Well Owner	CITY OF GARDEN CITY
Contractor	Downey Drilling, Inc. #748


Lithology

From	To	Lithology Intervals
0	5	topsoil,tan,soft
5	11	clay,brown,soft
11	46	sand & gravel,fine to coarse,gravelly,red,soft
46	74	clay,sandy,tan,soft
74	110	sand & gravel,fine to coarse,tan,soft
110	140	clay,fine to medium,sandy,tan,soft
140	186	sand & gravel,medium to coarse,red,soft
186	192	clay,fine to medium,sandy,tan,soft
192	200	sand & gravel,fine to coarse,red,soft

WATER RESOURCES
RECEIVED

MAR 27 2023

KS DEPT OF AGRICULTURE



PROJECT
CITY OF GARDEN CITY

COUNTY
FINNEY

LOGGED BY
ADAM

WELL NUMBER
MIDDLE - CHESTNUT

LAND LEGAL
NWSE 17-24S-32W

BOREHOLE DIA.
6.25"

DATE CONSTRUCTED
12/5/2022

TOTAL DEPTH
200'

GPS LOCATION
37.96528
-100.853391

DRILLER
RYAN

METHOD
STR MUD ROT

CASING

TYPE: FLUSH JOINT PVC

DIAMETER: 2"

LENGTH: 190' + 32"

SCREEN

TYPE: FLUSH JOINT PVC

DIAMETER: 2"

LENGTH: 10'

SLOT SIZE: 0.01

FILTER PACK

TYPE: #40 RED FLINT

AMOUNT: 1000LBS

GROUT

TYPE:

AMOUNT:

SEALS: AMT & TYPE:

BOT:

MID: 0-185'

TOP:

TYPE: 3/4" HOLE PLUG

SITE#: CHESTNUT

TH#: MIDDLE


WELL DEVELOPMENT

METHOD: AIR LIFT

DURATION: 1 HOUR

COMMENTS:

2X2 CONCRETE PAD
1 WELL PROTECTOR



WATER RESOURCES
RECEIVED
MAR 27 2023
KS DEPT OF AGRICULTURE

Account No. : 41160

Water Analysis Report

**DOWNEY DRILLING
PO BOX 278
LEXINGTON**

NE 68850-0278

**Invoice No. : 1392001
Date Received : 12/19/2022
Date Reported : 12/20/2022**

Lab Number : 30519

Results For : 22-1432

Location :

Sample ID : CN MIDDLE

pH	7.7
Total Dissolved Solids (TDS) Est, ppm	1644
Electrical Conductivity, mmho/cm	2.74
Cations / Anions, me/L	36.9 / 37.5

	<u>ppm</u>
Sodium, Na	263
Potassium, K	9
Calcium, Ca	350.6
Magnesium, Mg	92
Total Hardness, CaCO ₃	1261
Nitrate, NO ₃ -N	4.0 (SAFE)
Sulfate, SO ₄ -S	487
Chloride, Cl	111
Carbonate, CO ₃	< 1.0
Bicarbonate, HCO ₃	217
Total Alkalinity, CaCO ₃	179
Fluoride, F	0.14
Total Iron, Fe	< 0.01
Manganese, Mn	0.01

"<" - Not Detected / Below Detection Limit

Reviewed By : Raymond Ward

12/23/2022

Copy : 1

Page 1 of 8

1320 Research Park Drive
Manhattan, KS 66502
785-564-6700
www. agriculture.ks.gov



900 SW Jackson, Room 456
Topeka, KS 66612
785-296-3556

Mike Beam, Secretary

Laura Kelly, Governor

April 7, 2023

CITY OF GARDEN CITY , ATTENTION WATER DEPARTMENT
PO BOX 998 301 N 8TH ST
GARDEN CITY KS 67846

RE: File No(s). **519**

Dear Sir or Madam:

The Division of Water Resources (Division) has received your application(s) to change the place of use, point of diversion or use made of water for the file number(s) referenced above. Please be aware that the Division may have a large number of pending applications on hand at times and makes every attempt to process them in the order in which they are received. You will be contacted if additional information is required.

Please note, this letter only acknowledges receipt of your application(s) and does not guarantee approval. In accordance with the provisions of the Kansas Water Appropriation(s) Act, the use of water as proposed prior to approval of the application(s) is unlawful.

Additional information about the process may be found on our website at agriculture.ks.gov/divisions-programs/dwr. If you have any other questions, please contact our office at 785-564-6640 or your local Garden City Field Office at 620-276-2901. If you call, please reference the file number so we can help you more efficiently.

Sincerely,

A handwritten signature in black ink that reads "Kristen Baum". The signature is written in a cursive, flowing style.

Kristen Baum
New Applications and Changes Supervisor
Water Appropriation Program